

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-135-00559-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name R. W. Shields
Complete Address: 666 4th Natl Bk Bldg Wichita, Kans
Lease Name Pabst Well No. 1
Location NW NW SE Sec 24 Twp. 18 Rge. (E) (W) 21
County Ness Total Depth 4172
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Forbes Casing Pulling Co
Address: Great Bend, Kans License No. 49
Operation Completed: Hour 8AM Day 5 Month 8 Year 64

The Above well, was plugged as follows:

8 5/8" ~~88x~~ 1001' circulated with cement - 5 1/2" 4172' with 125 sax cement - PB to 4129' - Perf 4060'.

Filled with sand to 4050', set 4 sax cement with dump bailer - pulled approx 2040' 5 1/2" to 600' - pumped 15 sax gel & 71 sax weight mud to kill water flow - displaced 40 sax cement through 5 1/2" at 600' - heavy mud to 200' - displaced 40 sax cement through 5 1/2" at 200' - heavy mud to 40' - cement 40' to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/10/64
INV. NO. 9619-W

Signed: [Signature]
Well Plugging Supervisor