

15-077-20149-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217RECEIVED  
STATE CORPORATION COMMISSION  
NOV 8 11-8-72  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Hershberger Exploration

Complete Address Suite 230 Garvey East 200 W Douglas Wichita, Ks

Lease Name Atchibald Well No. 1

Location C SW/SE Sec. 11 Twp. 32 Rge. 9 (E) (W) W

County Harper Co. Total Depth 4430

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Clarke Oil Field Service

Address 107 W. Fowler Medicine Lodge, Ks License No. 583

Operation Completed: Hour 9:00 AM Day 6 Month 11 Year 1972

The above well was plugged as follows:

230 ft 8 5/8 surface pipe cement circulated. 4417 ft 4 1/2 long string  
cemented with 100 sacks. Top perf. 4417 ft. Sand to 4400 ft, 3  
sacks cement with bailer. Pulled 3300 ft 4 1/2. Set 10 ft rock bridge  
at 320 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: W. Russell Biharat  
Well Plugging Supervisor

INVOICED

DATE 11/8/72  
INV. NO. 6598-W