

15135-00367-0000

Form CP-3
Rev. 6-26-62

W
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Colorado Oil Co

Complete Address: Box 1030 Wichita, Kans

Lease Name Miner Well No. 1

Location CNW NW Sec. 33 Twp. 18 Rge. (E) (W) 21

County Ness Total Depth 4218

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling & Globe Cementing Co

Address: Chase, Kans License No. 436

Operation Completed: Hour 12 Noon Day 14 Month 9 Year 65

The Above well was plugged as follows:

8 5/8" 509' circulated with cement - 5 1/2" 4205' with 125 sax cement.

Sand to 4190', set 4 sax cement with dump bailer -

Pulled 2027' 5 1/2" to 800', circulated hole with heavy mud through 5 1/2"

at 800' (28 sax gel & 60 sax weight mud) displaced 30 sax cement

through 5 1/2" at 450', heavy mud to ^{160'} 200', displaced 30 sax cement through

5 1/2" heavy mud to 35', cement 55' to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edward Petty*
Well Plugging Supervisor

INVOICED
DATE 9/17/65
INV. NO. 1819-W