

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 25 1965  
8-25-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Leo J. Dreiling Oil Co

Complete Address: Victoria, Kansas

Lease Name Schniepp Well No. 1

Location GNE NE Sec. 32 Twp. 18 Rge. (E) (W) 21

County Ness Total Depth 4227

Abandoned Oil Well x Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kans License No. 396

Operation Completed: Hour 5:45 Day 23 Month 8 Year 65

The Above well was plugged as follows:

8 5/8" 301 Circulated with cement - 4 1/2" 4220' with 125 sax cement.  
sand back to 4200', set 4 sax cement with dump bailer - pulled 2535'  
4 1/2" to 900' pumped 54 sax gel and 75 sax weight mud to kill water flow,  
pulled 4 1/2" to 550', displaced 35 sax cement through 4 1/2" at 550',  
heavy mud to 150', displaced 35 sax cement through 4 1/2" at 150', heavy  
mud to 35' filled with cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 8/26/65  
INV. NO. 1698-W

Signed: Edward Petty  
Well Plugging Supervisor