

KANSAS

Form CP-3  
Rev. 6-26-62

40  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION  
FEB 13 1967  
2-13-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

15-135-20008-00-00

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Building Wichita, Kansas

Lease Name Price "B" Well No. L

Location: C SE NW Sec. 34 Twp. 18 Rge. 21 (E) (W) X

County Ness Total Depth 4264'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools Globe Cementing Co.

Address:  License No.

Operation Completed: Hour 10:45 A Day 10 Month 2 Year 1967

**The Above well was plugged as follows:**

RTD 4264' 8 5/8 csg set at 384' cwc 190 sc.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 20 sc

cement thru drill pipe. Heavy mud to 250' set cementing plug and displaced 25 sc

cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc

cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 2/13/67  
INV. NO. 4752-4

Signed: L. J. Massey  
Well Plugging Supervisor