

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 28 1966
11-28-66
CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sioux Petroleum, c/o W. F. Roland
 Complete Address: Drawer 270, Medicine Lodge, Kansas
 Lease Name Zimmerman Well No. # 3
 Location C SE SW Sec. 29 Twp. 32 Rge. 11 (E) (W) W
 County Barber Total Depth 3800'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated:
 Plugging Contractor: Hellar Drilling Company, Inc.
 Address: 1014 Union Center Bldg., Wichita, Kansas License No.
 Operation Completed: Hour 4:45AM Day 24th Month Nov. Year 1966

The Above well was plugged as follows:

213' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 200', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 200', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlie Elving
Well Plugging SupervisorDATE 11/29/66
INV. NO. 4344-W