

Me
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 10 1964
4-10-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mull Drilling Company

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name S. J. Davis Well No. # 1

Location NW NW SW Sec. 8 Twp. 32 Rge. 9 (E) (W) W

County Harper Total Depth 4349

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 2:30PM Day 2nd Month April Year 1964

The Above well was plugged as follows:

160' of 8 5/8" surface pipe, cemented with 100 sacks. 4349' of 5 1/2" long
string, cemented with 100 sacks. Top perferation 4313'. Bottom of hole
was sanded to 4300', and cemented with 5 sacks. Hole was filled with
mud to 250', with 10' rock bridge, and cemented with 50 sacks, bringing
the top of the cement to 110' in the surface pipe. Hole was filled with
mud to 40', with 10' rock bridge, and cemented with 10 sacks to base
cellar.

3400' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/10/64

INV. NO. 8926-W

Signed: Archie Elving
Well Plugging Supervisor