

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mobil Oil Company

Complete Address: P. O. Box 335, Attica, Kansas

Lease Name Ed Kircher Well No. # 2

Location NE NW NE Sec. 8 Twp. 32 Rge. 9 (E) (W)

County Harper Total Depth 4440

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Co.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 2:00PM Day 17th Month July Year 1963

The Above well was plugged as follows:

300' of 8 5/8" surface pipe, cement circulated with 225 sacks. 4439' of
5 1/2" long string, cemented with 200 sacks. Plugged back to 4408'. Top
perferation 4348'. Sanded to 4335', cemented with 5 sacks. Hole was
filled with mud to 250', 10' rock bridge, cemented with 20 sacks. Hole
was filled with mud to 40', 10' rock bridge, cemented with 10 sacks to
base cellar.

3100' of 5 1/2" long string recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7-19-63

JUL 19 1963

INV. NO. 7438-W

7-19-63
CONSERVATION DIVISION
Wichita, Kansas