

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

JAN 21 1966
1-21-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Kircher Well No. # 1

Location S/2 NE Sec. 8 Twp. 32 Rge. 9 (E) (W)

County Harper Total Depth 4364'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 11:30AM Day 17th Month Jan. Year 1966

The Above well was plugged as follows:

230' of 8 5/8" surface pipe, cement circulated. 4336' of 4 1/2" long string,
cemented with the top of the cement at 3805'. This is an open hole. Bottom
of the hole was sanded to 4300', and cemented with 3 sacks, through the
dump bailer. 700' of 4 1/2" long string was recovered from the hole. Fluid
in the hole was bailed down to 225', bridge plug and rock bridge from 225'
to 215, and cemented with 25 sacks. Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/21/66
INV. NO. 2633-W