


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

## WELL PLUGGING RECORD

NORTH

Locate well correctly on above  
Section Plat

Barber County, Sec. 14 Twp. 32 Rge. 15 (E) (W)  
Location as "NE/CNW/SE/SW" or footage from lines C NW NE  
Lease Owner Aylward Drilling Company  
Lease Name Skinner "Z" Well No. 3  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) 011  
Date well completed 4-11 19 65  
Application for plugging filed 9-15 19 71  
Application for plugging approved 9-17 19 71  
Plugging commenced 9/21/71 19  
Plugging completed 9/25/71 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production August 19 71  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hiberstein  
Producing formation Viola Depth to top 4978' Bottom Total Depth of Well 4987 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	274	none
				5 1/2"	4981	4268'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole to 4970', set 5 sacks of cement. Loaded hole with water, shot pipe at 4297', pulled 129 joints. Set rock bridge at 260' and ran 4 yards ready mix.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 30 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 19 71

My  MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

Notary Public.

## SKINNER "Z" #3

Casing Record: Company: Aylward Drilling Company et al Location: C NW NE  
 Contractor: Aylward Drilling Company Sec. 14-32-15W  
 8 5/8" - 274' Barber County  
 5 1/2" - 4981' Commenced: April 27, 1965 Kansas  
 Completed: May 11, 1965

Elevation: 2019 K.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Soil	0	30	Set 8 5/8" surface pipe @ 274'
Sand & Gyp Streaks	30	90	w/275 sacks.
Red Bed	90	150	
Gyp	150	190	Geological Tops:
Red Bed	190	1096	
Red Rock	1096	1180	Heebner 4102
Shale & Lime	1180	2050	Douglas 4134
Shale w/Lime Streaks	2050	2110	Brown Lime 4246
Lime	2110	2750	Lansing 4270
Shale	2750	2765	Choteau 4877
Shale & Lime	2765	2965	Kinderhook 4915
Shale w/Lime Streaks	2965	3025	Maquoketa 4949
Shale	3025	3765	Viola 4978
Shale & Lime	3765	4229	
Lime	4229	4775	DST 4710-45 Open 30"
Lime & Shale	4775	4810	Rec. 15' Mud
Lime w/Shale Streaks	4810	4895	IBHP 91#/30"-FBHP 58#/30"
Shale & Lime	4895	4958	FP 33-33#
Lime	4958	4987 T.D.	
			DST 4953-70 Open 30"
			Rec. 30' mud
			IBHP 33#/30"-FBHP 33#/30"
			FP 33-33#
			DST 4974-87 GTS/3"
			Gauged 367,000 CFG/5"
			Flowed oil in 55"
			IBHP 1678#/30"-FBHP 1607#/30"
			FP 274-612#
			Set 5 1/2" casing @ 4981 w/100 sax.
			No log run.

RECEIVED  
 STATE CORPORATION COMMISSION  
 9-17-71  
 SEP 17 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Frank Hamlin

Subscribed and sworn to before me this 14th day of May, 1965

Joseph A. Floss  
 Notary Public

My commission expires May 14, 1968