


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 10 Twp. 32 Rge. (E) 15 (W)
Location as "NE/CNW&SW&" or footage from lines NW NW NE
Lease Owner Aylward Drilling Company
Lease Name Skinner "W" Well No. 1
Office Address 909 First National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed May 23, 1958
Application for plugging filed July 6, 1966
Application for plugging approved July 6, 1966
Plugging commenced July 16, 1966
Plugging completed July 20, 1966
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production July 12, 1966
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Elving
Producing formation Mississippian Depth to top 4859 Bottom Total Depth of Well 4946 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	209'	None
				5 1/2"	4928'	2552'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand from 4946 to 4910 feet
5 sacks of cement from 4910 to 4875 feet
Bailed down to 200 feet, built wood bridge
Rock from 200 to 190 feet
25 sacks cement from 190 to 115 feet
Mud from 115 to 40 feet
Rock from 40 to 30 feet
10 sacks cement from 30 feet to top.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Oilfield Service, Inc.
Address Chapin Building, Medicine Lodge, Kansas 67104

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Frank Hamlin (employee of owner) or ~~owner~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Frank Hamlin

909 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of August, 1966

My commission expires June 10, 1970

Amy O. Brossette
Amy O. Brossette

Notary Public.

SKINNER "W" NO. 1

Casing Records:

8 5/8" - 209'
5 1/2" - 4928'

Company: Aylward Drilling Company,
Yale H. Lewis, et al
Contractor: Aylward Drilling Company

Commenced: May 6, 1958
Completed: May 23, 1958

Location: NW NW NE 10-32-15W
Barber County
Kansas

Elevation: 2002 RB

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand & Clay	0	65	Set 8 5/8" surface pipe @ 209' w/175 sacks cement.
Red Rock	65	150	
Red Rock & Gyp	150	940	Geological Tops:
Red Rock & Shale	940	1545	
Shale & Shells	1545	1950	Heebner Shale 4137
Shale & Lime	1950	2250	B/Oread 4176
Shale & Shells	2250	2270	Douglas Sand 4191
Lime	2270	2370	Lansing 4317
Lime w/some Shale	2370	2485	B/Kansas City 4764
Lime	2485	2743	Miss. 4859
Lime & Shale	2743	2840	T.D. 4946
Lime	2840	2940	DST 4842-4920 Open 30 min. Rec. 35' Mud. IBHP 28#/30", FBHP 40#/30". FP 28#-28#.
Lime w/Shale	2940	3150	
Lime & Shale	3150	3495	DST 4920-46 Open 2 Hr. 5 Min. Gas to surf./14", too wk. to gauge. Rec. 880' oil. IBHP 1570#/20", FBHP 1430#/30". FP 50#-285#.
Lime	3495	3570	
Lime & Shale	3570	3760	Set 5 1/2" casing @ 4928' w/75 sacks cement.
Lime	3760	3805	
Lime w/some Shale	3805	3907	RECEIVED STATE CORPORATION COMMISSION JUL 6 1966 7-6-66 GENERAL INVESTIGATION DIVISION WICHITA, KANSAS
Lime & Shale	3907	3991	
Shale & Lime	3991	4064	I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.
Lime & Shale	4064	4244	
Shale	4244	4286	Subscribed and sworn to before me this 16th day of July, 1958.
Sand & Shale	4286	4355	
Lime	4355	4691	DUANE JESSUP Notary Public
Lime & Shale	4691	4745	
Lime	4745	4770	My Commission expires December 11, 1961.
Lime w/Shale	4770	4809	
Lime w/Chert	4809	4835	
Lime	4835	4914	
Cherty Lime	4914	4946 T.D.	

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse

Subscribed and sworn to before me this 16th day of July, 1958.

Duane Jessup
DUANE JESSUP
Notary Public

My Commission expires December 11, 1961.