


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 7 Twp. 32S Rge. 15WE/4
Location as "NE/CNW1SW1/4" or footage from lines _____
990' FNL & 2310' FEL
Lease Owner Texas Oil & Gas Corp.
Lease Name Rusk "E" Well No. 1
Office Address 200 W. Douglas-Suite 300, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole
Date Well completed October 30, 1980
Application for plugging filed Verbal Application 19____
Application for plugging approved Verbal Approval 19____
Plugging commenced October 30, 1980
Plugging completed October 30, 1980
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Barnett
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,968'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	390'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,968 ft. (rotary total depth) to 410 ft. Set plug at 410 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 410 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Dowell Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dowell Div., Dow Chemical Co.
Hwy. 281 & Santa Fe, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent ~~XXXXXXXXXX~~ of owner ~~XXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water #10, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 80

Elsie Willison RECD
Elsie Willison - Notary Public.
STATE CORPORATION COMMISSION

My commission expires July 25, 1982

NOV 19 1980
11-19-80
CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.

SEC. 7 T-32S R-15W
 LOC. 990' FNL & 2310' FEL

FARM Rusk "E" NO. 1

COUNTY Barber

ROTARY TOTAL DEPTH 4,968'
 COMM. October 20, 1980 COMP. October 30, 1980
 CONTRACTOR H-30, INC. (Rig #5)
 ISSUED November 7, 1980

CASING

10 3/4"
 8 5/8" Set at 390' cemented w/350 sxs cement
 5 1/2"
 4 1/2"

ELEVATION 1,968' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Red Bed	409'
Red Bed	650'
Red Bed and Shale	2,202'
Anhydrite	2,415'
Shale and Lime	4,740'
Lime and Chert	4,829'
Shale and Lime	4,968'
Rotary Total Depth	4,968'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting

 Dean Britting

State of Kansas)
) ss:
 County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 7th day of November, 1980.

Elsie Willison

 Elsie Willison - Notary Public

My Commission Expires:
 July 25, 1982

RECEIVED
 STATE COMMISSION
 NOV 19 1980
 11-19-80
 CONSERVATION DIVISION
 Wichita, Kansas