

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

BARBER County, Sec. 13 Twp. 32 Rge. 15W(E) (W)
NE NE SE

Location as "NE/CNWSW" or footage from lines
Aylward Drilling Company

Lease Owner

Lease Name Swann Stump Smith "B" Well No. 1

Office Address Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Gas Well

Date well completed March 13 1957

Application for plugging filed November 22 1971

Application for plugging approved November 23 1971

Plugging commenced 12/23/71 19

Plugging completed 12/31/71 19

Reason for abandonment of well or producing formation depleted.


If a producing well is abandoned, date of last production November 1971

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein

Producing formation Mississippian Depth to top 4774 Bottom Total Depth of Well 4900 Feet

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	209	none
				5 1/2"	4899	3721'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, ran sand, tried to load hole, hole would not load.
Ran more sand and set 5 sacks of cement. Loaded hole with water.
Shot pipe at 3940', 3720', pulled 113 joints of 5 1/2" casing.
Set rock bridge 220' and ran 4 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RECE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO MARGARET MELCHER 31st day of December, 1971
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires Feb. 15, 1975
Margaret Melcher Notary Public.

STUMPH-SMITH "B" #1

Casing Records:

Company: Aylward Drilling Company
 Contractor: Aylward Drilling Company

Location: NE NE SE 13-32-15W
 Barber County, Kansas

8 5/8" - 209'
 5 1/2" - 4899'

Commenced: March 13, 1957
 Completed: March 31, 1957

Elevation: 2003' R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>	
Sand & gravel	0	40	Set 8 5/8" surf. pipe @ 209' with 200 sax cement.	
Sand	40	95		
Red rock	95	150	DST 4776-94 Open 1 1/2 hr. Gas to surf. in 49 min. Rec. 12" mud. FP 4# - 4#	
Gyp	150	175		
Red rock & bed	175	670	IBHP 1703#/30 min. FBHP 1688#/30 min.	
Red rock, shells & shale	670	984		
Red rock	984	1150	DST 4794-4824 Open 1 hr. Gas to surf. in 4 min. Gauged 734,000 CFG/5 min. & remained steady thereafter. Rec. 63' GCM	
Shale & shells	1150	1850		
Shale & lime streaks	1850	2100	FP 180# - 190#	
Lime	2100	2815		
Shale & lime	2815	2900	IBHP 1750#/30 min. FBHP 1750#/30 min.	
Lime & Shale	2900	3055		
Shale & sandy lime	3055	3220	DST 4834-66 Open 1 1/2 hr. Gas to surf. in 13 min. Gauged 76,000 CFG. Rec. 12" mud.	
Shale & lime	3220	3445		
Lime & shale	3445	3737	FP 30# - 35#. IBHP 1770#/30 Min.	
Shale	3737	3852		
Shale & lime	3852	4156	FBHP 1745#/30 min.	
Lime & shale	4156	4232		
Sand	4232	4264	GEOLOGICAL TOPS:	
Lime & shale	4264	4319		
Lime	4319	4794	Elgin Sand	None
Cherty Lime	4794	4824	Heebner	4100'
Lime	4824	4852	Base/Oread	4127
Lime & shale	4852	4866	Douglas Sand	4232
Lime	4866	4900 TD	Lansing	4264
			Mississippian	4774
			RTD	4900

Set 5 1/2" Casing @ 4899' with 150 sax cement.

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 23 1971
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse

Subscribed and sworn to before me this 6th day of April, 1957.

Duane Jessup
 DUANE JESSUP Notary Public

My commission expires December 11, 1957