

15-007-01608-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 22 Twp. 32S Rge. 15 (W)  
Location as "NE/CNWxSWx" or footage from lines SE NE SW  
Lease Owner Champlin Petroleum Company  
Lease Name Baird Well No. 1  
Office Address P. O. Box 308, Ellinwood, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Salt Water Disposal Well  
Date well completed (Disposal Well) November 22, 19 57  
Application for plugging filed September 7, 19 71  
Application for plugging approved September 8, 19 71  
Plugging commenced October 7, 19 71  
Plugging completed October 12, 19 71  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 5324 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4" OD	473'	None
				4 1/2"	5279'	800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 4900' and run 4 sacks of cement filling hole to 4870' filled with mud to 260' and set rock bridge to 250' and ran 5 yards of Ready Mix cement from 250' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 27 1971  
10-27-71  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Glenn & Smith Pipe Pulling Company  
Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. W. Meyers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Meyers, District Operations Manager  
P. O. Box 308, Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of October, 19 71



N. Kenneth Stivers  
Notary Public.

My commission expires 4/16/74

CHAMPLIN PETROLEUM COMPANY  
 BAIRD #1 SWDW  
 Located 1610' FSL & 2310' FWL  
Section 22-32S-15W, Barber County, Kansas

DRILLERS LOG

0- 140'	Redbed, Sand & Shale
500'	Redbed and Shells
825'	Redbed
840'	Anhydrite
1425'	Redbed & Shale
2050'	Shale & Shells
2130'	Shale - Lime
2435'	Lime
2525'	Lime & Shale
2560'	Lime
2705'	Lime & Shale
2765'	Lime
2815'	Lime & Shale
2990'	Shale & Lime
3050'	Lime & Shale
3115'	Shale & Lime
3380'	Lime & Shale
3435'	Lime
3535'	Shale & Lime
3600'	Lime & Shale
3780'	Shale & Lime
3835'	Lime & Shale
3870'	Shale & Lime
3960'	Lime & Shale
3985'	Lime
4300'	Shale & Lime
4320'	Lime
4360'	Lime & Shale
4675'	Lime
4980'	Lime & Shale
5040'	Lime
5063'	Lime & Chert
5088'	Lime & Sand
5101'	Chert & Sand
5115'	Sand, Chert & Shale
5125'	Shale
5147'	Sand & Shale
5215'	Shale - Lime
5324'	Lime

RECEIVED  
 STATE CORPORATION COMMISSION  
 9-8-71  
 SEP 8 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas