


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 11 Twp. 32 Rge. 15 ~~XXX~~ (W)
Location as "NE/CNW&SW&" or footage from lines NE NW NW
Lease Owner Aylward Drilling Company & Lewis Bros.
Lease Name Skinner "y" Well No. 1
Office Address 813 1st National Bank Bldg. - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 30 1957
Application for plugging filed September 30 1957
Application for plugging approved September 30 1957
Plugging commenced September 30 1957
Plugging completed September 30 1957
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5014 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	201'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with heavy mud from total depth to 200';
cement plug at 200' with 20 sacks of cement; heavy mud to 40';
cement plug to top of surface with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1957
10-22-57
CONSERVATION DIVISION
Wichita, Kansas.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Aylward Drilling Company
Address 813 1st National Bank Bldg. - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Paul W. Hesse (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse
813 1st National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of October, 1957

Duane Jessup
DUANE JESSUP Notary Public.

My commission expires December 11, 1957

PLUGGING
FILE SEC 11 T. 32 R. 15
BOOK PAGE 50 LINE 9

SKINNER "Y" NO. 1

Casing Record:
8 5/8" - 201'

Company: Aylward Drilling Company and
Yale Lewis
Contractor: Aylward Drilling Company

Location: NE NW NW
Section 11-32-15W
Barber County
Kansas

Commenced: September 13, 1957
Completed: September 30, 1957

Elevation: 1968 RB

	<u>From</u>	<u>To</u>	<u>Remarks</u>	
Sand	0	20	Set 8 5/8" surface pipe @ 201' w/165 sacks cement	
Red Bed	20	110		
Hard red rock	110	140	Geological Tops:	
Gyp and red rock	140	201		
Red rock and Gyp	201	1000		
Shale and shells	1000	2215		Heebner Shale 4156
Lime	2215	2295		Base/Oread 4197
Lime w/shale	2295	2395		Douglas Sand 4228
Lime w/some shale	2395	2525		Tonganoxie Sand 4325
Lime	2525	2595		Lansing 4351
Lime and shale	2595	2667		Base/Kansas City 4843
Lime w/shale	2667	2775		Basal Penn. Cong. 4941
Lime	2775	2835	TD 5014	
Shale w/lime	2835	2900		
Shale and lime	2900	2990		
Shale	2990	3255	DST 4842-95 Open 30 min. Very wk. bl. for 5 min. Rec. 25' mud. FP 40#-50# IBHP 55#/30 min., FBHP 60#/30 min.	
Shale with lime	3255	3380		
Shale	3380	3495		
Shale and lime	3495	3565		
Shale w/lime	3565	3700		
Shale and lime	3700	3780		
Shale w/lime	3780	3925		
Lime and shale	3925	3995		
Shale and lime	3995	4087		
Sandy lime w/shale	4087	4103		
Sand and shale	4103	4185		
Lime w/shale	4185	4272		
Lime and shale	4272	4331		
Lime	4331	4525		
Lime w/shale	4525	4584		
Lime	4584	5009		
Lime and shale	5009	5014 T.D.		

D & A

RECEIVED
CONSERVATION COMMISSION
OCT 22 1957
10-22-57
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse

Subscribed and sworn to before me this 10th day of October, 1957.

Duane Jessup
DUANE JESSUP Notary Public

My commission expires December 11, 1957

PLUGGING
FILE SEC 11 T 32 R 15W
BOOK PAGE 50 LINE 9