

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-077-20,777-0000

LEASE NAME Easterby

WELL NUMBER 1

2970 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 8 TWP. 32 RGE. 9 (E) or (W)

COUNTY Harper

Date Well Completed 4/20/82

Plugging Commenced 11/01/90

Plugging Completed 11/02/90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Edmiston Oil Co., Inc.

ADDRESS 125 N. Market, Suite 1250

PHONE#(316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil & Gas and SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 31, 1990 (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4328 Bottom T.D. 4380

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	285	-0-
				4 1/2	4379	2870'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded off to 4278', plugged w/4 sx common at 4278'; sanded off to 3500', plugged with 4 sx common. Shot off pipe at 2870', pulled out of hole. Set plug at 1450' with 35 sx, plug at 950' with 35 sx. Plug at 330' circulated to surface. Used total of 90 sacks common 60 sacks fly ash.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Edmiston Oil Co., Inc. License No. 5042

Address 125 N. Market, Suite 1260 Wichita, KS 67202-1774 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Edmiston Oil Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss. NOV 20 1990 11-20-90

Jon M. Callen


(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jon M. Callen

(Address) 125 N. Market, Suite 1260 Wichita, KS

SUBSCRIBED AND SWORN TO before me this 19th day of November, 19 90



Juliaenne Thompson
 Notary Public

Commission Expires: November 5, 1994