

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. MARKET, ROOM 2078  
 WICHITA, KANSAS 67202

WELL PLUGGING RECORD  
 K.A.R. -82-3-117

API NUMBER 15-077-21,296

LEASE NAME Greiving

WELL NUMBER 1-7

4620 Ft. from S. Section Line

3300 Ft. from E. Section Line

SEC. 7 TWP. 32S RGE. 9 (E) or (W)

COUNTY Harper

Date Well Completed 2-22-96

Plugging Commenced 3-26-96

Plugging Completed 3-27-96

TYPE OR PRINT  
 NOTICE: Fill out completely and  
 return to Cons. Div. office  
 within 30 days.

LEASE OPERATOR Bison Production Company

ADDRESS 9320 E. Central Wichita, Kansas

PHONE# (316) 636-1801 OPERATOR LICENSE NO. 31532

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The Plugging proposal was approved on 3-22-96 (date)

by Steve Van Gieson (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippi Depth to Top 4374 Bottom \_\_\_\_\_ T.D. 4470

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				5 1/2"	4459	3375'

RECEIVED  
 KANSAS SURP  
 APR 29 1996  
 209

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set

Dump 106' of sand from 4419' to 4313' dump 5 sx cement. Pump 35sx cement plug at 1638'. Pump 35sx plug at 905'. Pump 70 sx cement plug from 274' to surface.

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address Box 333 Attica, Ks. 67009

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bison Production Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Steven C. Anderson, Vice President, Production (Employee of Operator) or (Operator) on

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) \_\_\_\_\_  
 (Address) 9320 E. Central Wichita, Ks 67206

SUBSCRIBED AND SWORN TO before me this 1st day of April, 19 96

Sandra J. Boyd  
 Notary Public

My Commission Expires: May 13, 1996

