

15-077-00301-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Harper County, Sec. 6 Twp. 32 Rge. (E) 9 (W)
Location as "NE/CNW/SW" or footage from lines C S 1/2 NE 1/4 NW 1/4
Lease Owner Pickrell Drilling Company
Lease Name Fetrow Well No. 1
Office Address 705 4th National Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 20, 1963
Application for plugging filed October 20, 1963
Application for plugging approved October 20, 1963
Plugging commenced October 20, 1963
Plugging completed October 20, 1963
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Depth to top Bottom Total Depth of Well 4457 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	216'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 225'. Set plug. Cemented with
25 sacks cement. Heavy mud to 40'. Set plug.
Cemented with 10 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1963
10-28-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PICKRELL DRILLING COMPANY
Address 705 4th National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

C. W. SEBITS
705 4th Nat'l Bank Bldg, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of October, 1963

Maxine Blackman
Notary Public.

My commission expires June 21, 1966

15-077-00301-0000

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY Rotary Drilling Commenced 10-10-63
705 4th National Bank Bldg. Rotary Drilling Completed 10-20-63
Wichita, Kansas
LOCATION: Fetrow No. 1 - C S/2 NE/4 NW/4 Section 6-32-9W,
Harper County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: (9 jts) 8 5/8" surface casing set at 216', cemented with 150
sacks cement. Circulated. Completed 5:00 P.M. October 10,
1963. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

10	Sand	
216	Red Rock	C. F. S.
1080	Red Rock & Shale	4365
1520	Shale, Shells & Lime	
1690	Shale & Lime	
1875	Lime	Slope Test
2750	Lime & Shale	2500
2960	Lime	3000
3145	Lime & Shale	3500
3225	Lime	4000
3490	Lime & Shale	
3626	Lime, Shale & Sand	
4193	Lime	S. L. M.
4372	Lime & Shale	3821
4457	Mississippian - TD	4025
		4367

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1963
10-28-63
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 23rd day of October, 1963, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

[Signature]
Maxine Blackman Notary Public