


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Harper County. Sec. 5 Twp. 32 Rge. 9 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner. ~~XXXXXXXXXX~~ Shawver Armour, Inc.
Lease Name Carl Berry Well No. 1
Office Address 817 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed June 10 19 60
Application for plugging filed June 10 19 60
Application for plugging approved June 10 19 60
Plugging commenced June 10 19 60
Plugging completed June 10 19 60
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4432 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TO	SIZE	PUT IN	PULLED OUT
Surface	Water	-0-	199'	8-5/8"	199'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 190'
1 Plug 190' Howco Plug
1/4 sx hulls 15 sx cement
Thru drill pipe
Heavy mud to 35'
2 Plug 35' Howco Plug
1/4 sx hulls 10 sx cement in dry
Bridge rat hole @ 5' 2 sx in it cement

RECEIVED
STATE CORPORATION COMMISSION

JUN 24 1960
6-24-60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shawver Armour, Inc
Address 817 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James M. Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Armour
James M. Armour
817 Central Building
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of June, 19 60

My commission expires Dec. 29, 1963

Marjorie Hall
Marjorie Hall Notary Public.



DRILLER'S LOG

FARM NAME:	BERRY # 1	LOCATION:	SE SE NE Sec. 5-32S-9W Harper County, Kansas
CONTRACTOR:	Shawver Armour, Inc.	ELEVATION:	1515 K.B.
OWNER:	Shawver Armour, Inc.		
COMMENCED:	May 29, 1960	COMPLETED:	June 10, 1960
CASING RECORD:	199' 8 5/8"		135 sx cement 2 CC

FORMATION:

TOPS:

Red Bed	199
Red Keel & Shale	1099
Shale	1320
Lime & Shale	2140
Shale & Lime	2705
Lime & Shale	2820
Lime	2880
Lime & Shale	3555
Sand	3603
Lime	3610
Lime Lansing	3755
Lime	3848
Kansas City Lime	3995
Lime	4057
Kansas City Lime	4094
Lime & Shale	4376
Mississippian Chert & Lime	4399
Lime & chat	4423
Mississippian Lime & chat & Chert.	4432
Rotary Total Depth	4432

Lansing	3609
Mississippian	4353

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1960
6-24-60
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
)

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER ARMOUR, INC.

BY James M. Armour
James M. Armour

Subscribed and sworn to before me this
10th day of June, 1960.

My commission expires Dec. 29th, 1963

Marjorie Hall
Marjorie Hall, Notary Public