

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber

County. Sec. 7 Twp. 32 Rge. 13 ~~XXX~~ (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner Aylward Drilling Company

Lease Name Brook Well No. 1

Office Address 813 1st Nat'l Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 13 1956

Application for plugging filed October 13 1956

Application for plugging approved October 13 1956

Plugging commenced October 13 1956

Plugging completed October 13 1956

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Pratt, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5012 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	206'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from T.D. to 200'; cement plug from 200' to 150' with 20 sacks of cement; heavy mud from 150' to 35'; cement plug from 35' to top of surface with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aylward Drilling Company

Address 813 1st Nat'l Bank Bldg., Wichita, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss. Paul W. Hesse (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse

813 1st Nat'l Bank Bldg., Wichita, Kansas
(Address)


SUBSCRIBED AND SWORN TO before me this 15th day of October, 1956

My commission expires December 15, 1957



CONSERVATION DIVISION
Wichita, Kansas

Duane Jessup
Notary Public.



BROOK #1

Casing Records:

Company: Aylward Drilling Company
 Contractor: Aylward Drilling Company

Location: SW SW NE
 Section 7-32-13W
 Barber County, Kansas

8 5/8" - 206'

Commenced: September 21, 1956
 Completed: October 13, 1956

Elevation: 1771 RB

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Red Bed	0	192	Set 8 5/8" Surf. Pipe @ 206' w/150 sx cement
Red Bed & Sand	192	600	
Red Rock	600	960	DST 3920-51 Open 1 hr. Good blow throughout.
Red Bed & Sand	960	1175	Rec. 1270' SW. ISIP 1455#/20 min. FP 135# -
Sand & Shale	1175	1361	715#. FBHP 1405#/30 min.
Shale & Lime	1361	1849	
Lime	1849	1975	DST 4418-56 Open 1 1/2 hrs. Good blow dec. to
Shale & Lime	1975	2168	weak. Rec. 20' Oil Specked Mud. ISIP 350#/20
Lime	2168	2285	min. FP 45#-45#. FBHP 70#/30 min.
Shale & Lime	2285	2360	
Lime	2360	2435	DST 4748-57 Open 40 min. No blow. Rec. 7' mud.
Shale & Lime Streaks	2435	2590	ISIP 0#/30 min. FP 0#. FBHP 0#/15 min.
Shale & Lime	2590	2770	
Shale & some Lime	2770	2831	DST 4890-4902 Open 1 1/2 hrs. Fair blow dec. to
Shale & Lime	2831	3352	weak. Rec. 7' mud. ISIP 155#/20 min.
Lime	3352	3413	FP 30# - 25#. FBHP 75#/30 min.
Lime & Shale	3413	3759	
Lime	3759	3853	Geological Tops:
Sand & Lime	3853	3933	Huebner 3772
Lime, Shale & Sand	3933	3951	Toronto 3795
Sand & Lime	3951	4000	Douglas Sand 3933
Sand, Shale & Lime	4000	4038	Lansing 3965
Lime	4038	4093	B/Kansas City 4370
Lime & Shale	4093	4166	Mississippian 4463
Lime	4166	4259	Kinderhook 4674
Lime & Shale	4259	4331	Chattanooga Shale 4722
Lime & some Shale	4331	4375	Viola 4745
Lime & Shale	4375	4427	Simpson Shale 4860
Lime	4427	4530	Simpson Sand 4894
Lime & Shale	4530	4636	Arbuckle 4972
Lime	4636	4662	R.T.D. 5012
Lime & Shale	4662	4697	
Lime	4697	4719	
Lime & Shale	4719	5000	
Arbuckle	5000	5012 RTD	D. & A.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. [Signature]

Subscribed and sworn to before me this 17th day of October, 1956.

Duane Jessup
 Notary Public

My commission expires December 11, 1957

RECEIVED
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 7-32-13W
 BOOK PAGE 107 L F 41