

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber

County, Sec. 12 Twp. 32S Rge. 15 (E) (W)

Location as "NE/CNWxSWx" or footage from lines SE NW NE  
Lease Owner National Cooperative Refinery Association  
Lease Name Skinner "E" Well No. 1  
Office Address 305 Rule Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 27, 19 57  
Application for plugging filed April 29, 19 57  
Application for plugging approved April 29, 19 57  
Plugging commenced April 27, 19 57  
Plugging completed April 27, 19 57  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5050 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	241'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 240'. Set Bridge plug and 20 sacks cement. Filled hole with extra heavy rotary mud from 165' to 35', set bridge plug and 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 4 - 1957  
5-4-57  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Capitt Drilling, Inc.  
Address 811-16 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)  
305 Rule Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 1957

My commission expires November 26, 1960.

Nell McComb Notary Public.

PLUGGING  
FILE SEC. 12 T. 32 R. 15 W  
BOOK PAGE 9 LINE 12

## ROTARY DRILLING LOG

OPERATOR: National Cooperative Refinery Assn.  
 Skinner "E" #1  
 SE NW NE Sec. 12-32S-15W  
 Barber County, Kansas

CONTRACTOR: Capitt Drilling, Inc.  
 COMM: 4/5/57  
 COMP: 4/27/57

Remarks: Set 233.42' of 8-5/8" surface casing at 241.42' cemented with 175 sacks common cement, 2% C.C.

## Formations:

Sand	60'
Red Rock	140'
Lime	180'
Red Rock & Shells	1275'
Red Rock & Lime Shells	1780'
Red Rock & Lime Strks	2108'
Lime	2695'
Lime & Shale (Brks.)	2797'
Lime & Shale	3120'
Shale	3330'
Lime	3410'
Lime & Shale	3478'
Lime & Shale Brks.	3565'
Lime	3645'
Lime & Shale (Brks.)	3745'
Lime	3835'
Lime & Shale	3890'
Lime	4100'
Shale	4142'
Shale & Lime	4202'
Shale & Sand	4234'
Lime	4845'
Lime & Shale	4862'
Lime	4924'
Lime & Shale	4945'
Lime & Chert	4972'
Lime	5010'
Sandy Lime	5020'
Sand	5050'
Rotary Total Depth (D&A)	5050'

We certify the above log is true and correct to the best of our knowledge and belief.

CAPITT DRILLING, INC.

*R. R. McNicol*  
 R. R. McNicol

RECORDED  
 STATE COMMISSION

5-4-57

PLUGGING  
 FILE SEC. 12 T. 32 R. 15W  
 BOOK PAGE 9 LINE 12