

WELL RECORD

WALTER E. MARCHAL NO. 1

Date Spudded: May 12, 1943
Drig. Completed: June 20, 1943
Date Plugged: June 25, 1943

Location: 330' North and 330' West
of the Southeast corner of Sec. 2,
Twp. 32S, Rge. 15W, Barber County, Kan.

FROM	TO	FORMATION
0	70	Surface soil & sand
70	225	Shale & shells
225	600	Sand & shale
600	625	Shale
625	715	Shale & shells
715	800	Shale & lime shells
800	1150	Shale & shells
1150	1330	Shale & salt
1330	1410	Salt
1410	1600	Shale & shells
1600	1895	Lime
1895	2005	Lime & shale
2005	2140	Lime
2140	2200	Shale
2200	2315	Lime
2315	2395	Lime & shale
2395	2410	Lime
2410	2615	Shale
2615	2620	Shale & lime
2620	2640	Lime

FROM	TO	FORMATION
2640	2695	Lime & shale
2695	3275	Lime
3275	3755	Shale & lime
3755	4037	Lime
4037	4080	Lime, Chert & Pyrite
4080	4172	Lime & chert
4172	4190	Shale
4190	4245	Lime & chert
4245	4275	Lime
4275	4293	Lime & chert
4293	4344	Chat
4344	4375	Lime
4375	4395	Lime & chert
4395	4404	Chert
4404	4411	Lime & chert
4411	4455	Shale & lime
4455	4519	Shale
4519	4541	Shale & lime
4541	4560	Lime

T. D. 4560' in Viola Line

Elevation 1560'

Ran 600' of 10-3/4" OD 23# 3 Gauge Amoco Spiral Weld casing; set at 599';
cemented with 500 sacks of cement.

Top of Mississippi Chat 4294' - no show of oil.
Base of Mississippi Lime 4447' - no show of oil.
Top of Viola Line 4541' - no show of oil.

Ran Schlumberger Survey test - no commercial show of oil.

Plugged and abandoned - June 25, 1943.

Total Depth - 4560' in Viola Line.

Note: All above footages are calculated from the ground level.

I, the undersigned, being first duly sworn, upon oath, state that
this Well Record is true, correct and complete, according to the records in
this office, and to the best of my knowledge and belief.

W. L. Quinn
District Superintendent - West Kansas Dist.

Subscribed and sworn to before me this 7th day of July, 1943.

My Commission expires October 21st, 1944

Louis McQuinn
Notary Public

FLD-RDM 7/7/43
LPG (3)
Corporation Comm. (1)
Ohio Oil Company (2)
Sinclair-Prairie Oil Company (1)
File (1)

2 22 13W
80 36