

15735-19106-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 24 Twp. 18S Rge. 21 (E) (W) X

Location as "NE/CNWSW" or footage from lines SE NE NW

Lease Owner Four Way Operating, Inc.

Lease Name Pabst Well No. A-2

Office Address P. O. Box 698 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 6-30-69 19

Application for plugging approved 7-1-69 19

Plugging commenced 7-2-69 19

Plugging completed 7-19-69 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey

Producing formation Depth to top Bottom Total Depth of Well 4158 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1289	None
				5 1/2	None	3168

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cleaned out cellar. Moved in. Rigged up unit. Plugged bottom back to 4050' with sand. Dumped 5 sacks of cement.

Loaded hole with water. Working pipe.

Shot pipe at 3635' - 3540' - 3430' and 3550'. Circulating. Spotted 65 bbl of oil.

Working pipe - 25" stretch at 2500#. Working pipe. Shot pipe at 3193'.

Pulling pipe.

Set plug at 435'. Build 15' rock bridge.

Plugged well with 6 yards of ready mix cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of July, 1969

My commission expires May 27, 1973

Notary Public.

EXPLORATION RECORD

15-135-19106 ~~0000~~

Lease Pabst "A"

Well 2

SE NE NW Sec. 24-18S-21W		Ness County, Kansas		
Formation Name	Top	Base	Remarks	
Drilled by Phillips Petroleum Company				Casing Record
Clay & soil	0	55	8 5/8 at 1289'	880 sx Pozmix
Sand & shale	55	280	5 1/2 at 4156'	40 sx Bulk
Shale	280	480		
Sand	480	530		
Red bed & shale	530	740		
Sand	740	1000		
Shale & red bed	1000	1250		
Red bed	1250	1310		
Anhydrite	1310	1345		
Shale & shells	1345	1855		
Shale & lime	1855	2330		
Lime & shale	2330	2380		
Lime	2380	2605		
Lime & shale	2605	2875		
Lime	2875	3120		
Shale & lime	3120	3255		
Lime	3255	3910		
Lime & shale	3910	3980		
Lime	3980	4035		
Black shale	4035	4045		
Lime & sand	4045	4075		
Sand & shale	4075	4128		
Shale & M.Chert	4128	4158		
T.D.		* 4158 *	Producing formation penetrated	
PBTD		4126	at 4158.	
 <u>FORMATION TOPS - Welox</u>				
Heebner	3544		I, James W. Rockhold, certify this is a true and correct copy of the Driller's Log for the well drilled in the SE NE NW Section 24-18S-21W, Ness County, Kansas, to the best of my knowledge and belief. <u>FourWay Operating, Inc.</u>	
Toronto	3562			
LKC	3588			
Drum	3743			
Base LKC	3878			
Marmaton	3888			
Cherokee	4036			
Cherokee Sand	4065			
Mississippian	4136			

James W. Rockhold

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1969
CONSERVATION DIVISION
Wichita, Kansas