


STATE OF KANSAS  
CORPORATION COMMISSION

### WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

NESS County. Sec. 24 Twp. 18S Rge. 21 (E) (W) est  
Location as "NE/CNW/SW" or footage from lines NW SE NW  
Lease Owner R. W. Shields  
Lease Name Pabst "A" Well No. #2  
Office Address 308 Rule Building, Wichita, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 10, 1959  
Application for plugging filed November 27, 1961  
Application for plugging approved November 28, 1961  
Plugging commenced November 30, 1961  
Plugging completed December 21, 1961  
Reason for abandonment of well or producing formation Non-commercial

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker, Victoria, Kansas  
Producing formation Cherokee Sand Depth to top 4031' Bottom \_\_\_\_\_ Total Depth of Well 4145' Feet  
Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUR IN	PULLED OUT
				5 1/2"	4144'	2501'
				8-5/8"	1317'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded up to 200 ft.  
Set 10 Ft. rock bridge - 25 sacks cement  
Mudded hole to 35 ft.  
Capped hole ± 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 23 1966  
3-23-66  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Central Pipe Pulling Co.  
Address 1416 Coolidge - P. O. Box 656 - Great Bend, Kansas.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Norman J. Shields (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Norman J. Shields  
308 Rule Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 1966  
Helen E. McClintick  
Notary Public.

My commission expires July 6, 1969

DRILLERS' LOG

15135 00560 0000

Well Owner: R. W. Shields  
Farm Name: Pabst Well No. 2  
Commenced: 7/27/59  
Completed: 8/10/59  
Total Depth: 4145'  
Casing: 8 5/8" @ 1317' cemented  
5 1/2" @ 4144' cemented

NW SE NW  
Sec. 24-18S-21W  
Ness County, Kansas  
Elevation:  
Production:

Contractor: Peel Brothers, Inc.

Figures below indicate bottoms of formations:

Clay & sand	0 -	80
Shale		315
Sand		370
Shale & shells		645
Sand		695
Shale & shells		725
Sand		750
Shale & shells		750
Sand & shale		980
Shale		1020
Shale & shells		1110
Blue shale		1270
Anhydrite		1315
Shale & shells		1345
Shale & lime		1850
Lime		2125
Lime & shale		2420
Lime		2520
Lime & shale		2614
Lime		3205
Lime & sand		4050
Sand		4075
Hard sand & shale		4090
Shale		4110
Miss. chert		4125
Total Depth		4145
		4145

RECEIVED  
STATE CORPORATIONS COMMISSION

MAR 23 1966

CONSERVATION DIVISION  
Wichita, Kansas

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY: Jack Mattick

SUBSCRIBED AND SWORN to before me this 11th day of August, 1959

My commission expires: April 27, 1960

Ruth Brant  
Notary Public