


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 24 Twp. 18 Rge. (E) 21 (W)
Location as "NE/CNW4SW4" or footage from lines 990' FSL and 2310' FWL
Lease Owner Phillips Petroleum Company
Lease Name Fabst "A" Well No. 3
Office Address Box 779 - Gt. Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 7, 1959 19
Application for plugging filed September 7, 1959 19
Application for plugging approved September 7, 1959 19
Plugging commenced September 7, 1959 19
Plugging completed September 7, 1959 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation Mississippi Depth to top 4128 Bottom 4151 Total Depth of Well 4151 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Dry	3528		8 5/8"	1298.56	None
Toronto	Dry	3546				
LKC	Dry	3573				
Drum	Dry	3731				
Base LKC	Dry	3860				
Marmaton	Dry	3870				
Cherokee	Dry	4020				
Mississippi	Dry	4128				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 25 sx. common cement at 4151' in filling to 4072'. Mudded hole to 1311'.
Spotted 25 sx. common cement at 1311' in filling to 1233'. Mudded from 1288'
to 40'. Set wood plug at 40' and dumped 10 sx. cement in filling to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight & Smith Drilling Company - Rotary Contractor
Address Great Bend, Kansas.

STATE OF KANSAS COUNTY OF BARTON, ss.
A. J. Willis (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 779 - Gt. Bend, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of September, 1959

My commission expires 11/18/61 Joseph M. Beal Notary Public.

PLUGGING
File Sec. 24 T. 18 R. 21W
Book Page 2 Line 15

1 Bylle
 2 WE McHugh
 1 File

EXPLORATION RECORD

15-135-00558-0000

Lease Pabst "A"

Well 3

Formation Name	Top	Base	Remarks
Shale Clay and Sand	0	180	
Sand	180	210	
Shale and Shells	210	410	
Sand	410	435	
Sand and Shale	435	515	
Red bed Shale and Shells	515	700	
Sand and shale	700	965	
Shale and Shells	965	1145	
Red bed and sand	1145	1260	
Red bed	1260	1295	
Anhydrite	1295	1330	
Red bed and shale	1330	1350	
Shale	1350	1392	
Shale and Shells	1392	1820	
Shale and lime	1820	2170	
Shale and Shells	2170	2320	
Lime	2320	2590	
Lime and shale	2590	3160	
Lime	3160	3865	
Lime and shale	3865	3923	
Lime	3923	3986	
Lime and Shale	3986	4021	
Shale	4021	4045	
Lime	4045	4056	
Sand	4056	4060	
Sandy lime	4060	4088	
Lime sand and shale	4088	4131	
Miss	4131	4147	
Miss lime	4147	4151	
Total Depth		4151 - Dry Hole	
FORMATION TOPS - Welox			
Hebner	3528		
Toronto	3346		
LKC	3573		
Drun	3731		
Base LKC	3860		
Marmaton	3870		
Cherokee	4020		
Cherokee Sand	4052		
Mississippian	4128		
P L U G G I N G			
File Sec.	<u>24</u>	<u>18</u>	<u>R21W</u>
Book Page	<u>2</u>		<u>15</u>

RECEIVED
 STATE CORPORATION COMMISSION

SEP 10 1959
 CONSERVATION DIVISION
 Wichita, Kansas