

15-007-00229-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

BARBER

County. Sec. 22 Twp. 32 Rge. 14 ~~00~~ W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner PETROLEUM, INC.

Lease Name HOAGLAND "A"

Well No. 1

Office Address ROUTE #2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed OCTOBER 3 19 56

Application for plugging filed OCTOBER 5 19 56

Application for plugging approved OCTOBER 3 19 56

Plugging commenced OCTOBER 3 19 56


Plugging completed OCTOBER 3 19 56

Reason for abandonment of well or producing formation

NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production NONE 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. RIVES, BOX 8, PRATT, KANSAS

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4735 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"OD	284'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUD UP WITH HEAVY MUD TO 280', PUSHED DOWN 1/4 SACK HULLS TO 280' FOLLOWED BY WOODEN PLUG. PLACED 20 SACKS CEMENT THROUGH DRILL PIPE ON TO PLUG. MUD UP TO 35' AND PLACED 1/4 SACKS HULLS AT 35' FOLLOWED BY WOODEN PLUG AND 10 SACKS CEMENT TO BASE OF WELL CELLAR.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY

Address ROUTE #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE

(employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Don Searle

ROUTE #2, GREAT BEND, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 10TH day of OCTOBER 19 56

Jed L. Brown

Notary Public.

My commission expires JULY 11, 1960

PLUGGING
FILE SEC. 22 T. 32 R. 14 W
BOOK PAGE 105 LINE 5

OCT 12 1956
10-12-56
CONSERVATION DIVISION
WICHITA, KANSAS

15-007-00279-0000
WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 22 T.32S R.14W

FARM HOAGLAND 'A' NO. 1


LOC. SE,SE,SW

TOTAL DEPTH 4735'

COUNTY Barber Co., Kansas

COMM. September 18, 1956 COMP. October 3, 1956

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 284' W/200 sax.

ELEVATION 1879' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

50	Red bed & gyp	Heebner	3938'
65	Gyp	Douglas	4091'
284	Red bed & gyp	Lansing	4120'
880	Red bed	Miss. Chirt	4634'
1050	Shale & shells		
1120	Red bed & shale		
1420	Shale		
1960	Shale & shells		
2010	Sand & shale		
2075	Shale & lime		
2260	Lime		
2317	Sandy lime & shale W/pyhrite streaks.		
2350	Lime & shale		
2472	Lime		
3545	Lime & shale		
3749	Shale		
3805	Lime		
3880	Shale		
3890	Lime		
3995	Shale & lime streaks		
4103	Shale & shells		
4115	Sand & shale		
4120	Sand		
4575	Lime		
4615	Lime & shale		
4634	Lime		
4655	Chirt		
4684	Lime		
4705	Lime & chirt		
4735	Lime		
4735	T. D.		

State of KANSAS }
County of BARTON } SS:

PLUGGING
FILE SEC. 22 T. 32 R. 14W
BOOK PAGE 105 LINE 5

I, Verne A. Morris of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Hoagland 'A' well

Verne A. Morris

Subscribed and sworn to before me this 9th day of October 19 56

My Commission Expires: July 11, 1960

Zed A. Brown
NOTARY PUBLIC