

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas


File

15-BS-0067-0000

WELL PLUGGING RECORD

Ness County, Sec. 35 Twp. 18 Rge. 21 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines CNE SE/4
Lease Owner Stickle Drilling Company
Lease Name Ryersee Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12-29-60 _____ 19____
Plugging completed 1-2-61 _____ 19____
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4224 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	352'	None
				5-1/2"	4223'	3285'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4224' and found it clear.
Sanded hole from 4224' to 4090' and dumped
4 sacks of cement @ 4090' with dump bailer.
Pulled 5 1/2" casing to 250' and pumped 20
sacks of jell mud through 5 1/2" casing.
Pulled balance of 5 1/2" casing and pumped in
100 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

1-10-61
JAN 10 1961

CONSERVATION DIVISION
WIC.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (~~owner of property~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 1961

My commission expires May 20, 1964 Milton J. Volun Notary Public.



Stickle Drilling Company Etal
Tulsa, Oklahoma

15135-00567-0000
Tulsa, Oklahoma
April 3, 1958

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: March 18, 1958
Drilling Completed: April 1, 1958

Ryersee "B" E/2 SE/4
Section 35-18S-21W,
Ness County, Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation

Surface	0
Shale	354
Shale & Red Bed	740
Sand & Shale	980
Shale & Shells	1795
Lime & Shale	2090
Shale & Shells	2160
Shale & Lime	2230
Lime & Shale	2770
Shale & Lime	3040
Lime & Shale	3330
Lime	3465
Lime & Shale	3570
Lime	3610
Lime & Shale	3695
Lime	3790
Lime & Shale	3832
Lime	3925
Lime & Shale	4140
Sandy Shale & Lime	4153
Conglomerate	4170
Mississippi	4178
Cherty Lime	4220

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Stickle Drilling Company Etal - Ryersee "B" E/2 SE/4 Section 35-18S-21W, Ness County, Kansas.

Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires

Frank E. Stickle
Frank E. Stickle

STATE

DEC 2
CONSERVATION DIVISION
Wichita, Kansas