


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 35 Twp. 18 Rge. 21 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW/4
Lease Owner Stickle Drilling Company
Lease Name Lang Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10-16-61 _____ 19____
Plugging completed 10-19-61 _____ 19____
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4255 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	290'	None
				5-1/2"	4253'	3436'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4196', sanded to 4150' and dumped 5 sacks of cement @ 4150' with dump bailer. Pulled 5 1/2" casing to 550', pumped in 20 sacks of mud and 20 sacks of cement. Pulled 5 1/2" casing to 170' and pumped in 20 sacks of cement. Pulled balance of 5 1/2" casing, set 10' rock bridge from 40' to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
10-27-61
OCT 27 1961

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of October, 19 61

My commission expires May 20, 1964

Milton J. Volin
Notary Public.

Stickle Drilling Company, et al
Tulsa, Oklahoma

15735-00067-0000
Tulsa, Oklahoma
September 7, 1956

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: August 15, 1956
Drilling Completed: September 1, 1956

Lank #1 - SE NW SW
Section 35-18S-21W,
Ness County, Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation

Rock & Sand	72
Shale & Shells	735
Sand	1070
Shale	1385
Anhydrite	1370
Shale	1415
Shale & Shells	2140
Lime & Shale	2655
Shale & Lime	2900
Lime & Shale	3470
Lime	3510
Lime & Shale	3545
Lime	3960
Lime & Shale	4030
Lime	4086
Lime & Shale	4128
Coring - No Record	4172
Sand	4174
Coring - No Record	4212
Lime & Chert	4255 TD

RECEIVED
OIL CORPORATION COMMISSION
SEP 25 1956
CONSERVATION DIVISION
Wichita, Kansas

I, Frank E. Stickle, hereby certify the above to be a true and complete Driller's Log of Stickle Drilling Company, et al's, Lank #1 - SE NW SW of Section 35-18S-21W, Ness County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires