

15-007-02638-0000

- 1 - State
- 1 - B. A. Conner
- 1 - Mary Crump
- 1 - File

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 245 North Water  
 WICHITA, KANSAS 67202

Rev. 6-3-74  
 FORM CP-1

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 16 1982  
 9-16-82  
 CONSERVATION DIVISION  
 Wichita, Kansas

WELL PLUGGING APPLICATION FORM  
 File One Copy

API Number 15 - 624 (of this well)

Lease Owner Phillips Petroleum Company 5229

Address Box 287 - Great Bend, Ks. 67530

Lease (Farm Name) Coultas "A" Well No. 1

Well Location SE NE Sec. 16 Twp. 32S Rge. (E) 15 (W)

County Barber Total Depth 4915 Field Name Perry Ranch

Oil Well      Gas Well X Input Well      SWD Well      Rotary D & A     

Well Log attached with this application as required yes

Date and hour plugging is desired to begin October 5, 1982

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

C. D. Dohrer Address Box 287 - Great Bend, Ks. 67530

Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 176 Chase, Kansas 67524

Invoice covering assessment for plugging this well should be sent to:

Name C. D. Dohrer - Phillips Petroleum Company

Address Box 287 - Great Bend, Ks. 67530

and payment will be guaranteed by applicant or acting agent.

Signed: C. D. Dohrer  
 Applicant or Acting Agent

Date: 9/15/82

State of Kansas



IN CARLIN  
 J. LOUX  
 G. T. ROY  
 LIP R. DICK  
 OL J. LARSON

Governor  
 Chairman  
 Commissioner  
 Commissioner  
 Executive Secretary

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 200 Colorado Derby Building  
 202 West 1st Street  
 WICHITA, KANSAS 67202

THIS PERMIT

September 21, 1982

DEC 21 1982

EXPIRES

WELL PLUGGING AUTHORITY

Coultas 'A' #1  
 SE NE  
 Sec. 16-32S-15W  
 Barber  
 T.D. 4915'  
 Kelso Casing


Phillips Petroleum Company  
 Box 287  
 Great Bend, KS 67530

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,

  
 DELBERT J. COSTA, Administrator

Mr. J. H. Metz Box 55, Stafford, KS 67578 (316) 234-6930  
 is hereby assigned to supervise the plugging of the above named well

NOTE: If you are unable to contact District Plugging Agent at his regular number, call TOLL FREE 1-800-362-1358.

Corrected copy.

D R I L L E R S   L O G

#1 Marsh-Coultas

|  |                                   |  |
|--|-----------------------------------|--|
| CASING RECORD:<br>232' of 8-5/8"<br>surface casing | COMPANY: Time Petroleum Company   | DESCRIPTION: C/NW NW<br>Section 16-32-15W<br>Barber County, Kansas |
| TOTAL DEPTH:<br>4915'                              | CONTRACTOR: Strata Drilling, Inc. |  |
|  | COMMENCED: January 4, 1962        |  |
|  | COMPLETED: January 20, 1962       |  |

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u>   |
|------------------|-------------|-----------|--|
| Red Bed          | 0           | 545       | Ran 224' of 8-5/8" surface casing; set and cemented at 232' with 175 sacks of regular cement, 2% gel. Plug down at 3:45 A. M. January 6, 1962. |
| Shale            | 545         | 1860      |  |
| Shale & Lime     | 1860        | 3961      |  |
| Sand & Shale     | 3961        | 4000      |  |
| Lime & Shale     | 4000        | 4170      |  |
| Shale            | 4170        | 4185      |  |
| Lime & Shale     | 4185        | 4287      |  |
| Lime             | 4287        | 4435      |  |
| Lime & Chalk     | 4435        | 4490      |  |
| Lime             | 4490        | 4740      |  |
| Lime & Shale     | 4740        | 4794      |  |
| Chert            | 4794        | 4800      |  |
| Chert & Lime     | 4800        | 4842      |  |
| Chert            | 4842        | 4878      |  |
| Chert & Lime     | 4878        | 4895      |  |
| Chert            | 4895        | 4915      |  |

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 16 1962  
9-16-62  
CONSERVATION DIVISION  
Wichita, Kansas

Total Depth 4915'

Ran Welex Log.

Ran 153 Joints used 4 1/2" pipe; set and cemented at 4914 1/2' with 300 sacks of regular cement and 2% gel. Lost circ. when started. Plug down at 12:45 A. M. January 20, 1962.

STATE OF KANSAS    )  
                          ) ss.  
COUNTY OF BARTON )

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Ralph Schuyler*  
-----  
Ralph Schuyler

Subscribed and sworn to before me this 22nd day of February, 1962.

*Elaine H. Taylor*  
-----  
Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1965