

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 077-20.823-0000

LEASE NAME Hospital

WELL NUMBER #3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 24 TWP. 32 RGE. 9 (S) or (W)

COUNTY Harper

Date Well Completed 1-21-83

Plugging Commenced 10-91

Plugging Completed 10-29-91

LEASE OPERATOR Attica Gas Venture Corp.

ADDRESS 123 N. Main Attica, KS 67009

PHONE# (316) 254-7222 OPERATORS LICENSE NO. 5039

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-29-91 (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Douglas Depth to Top 3416' Bottom 3458' T.D. 4850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION  
11-14-91

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi oil/water	4416' to 4425'	Surface	345'	8 5/8"	345'	-0-
Stalaker gas/water	3695' to 3700'	Surface	4550'	5 1/2"	4550'	2617'
Douglas gas/water	3416' to 3458'					

NOV 14 1991

CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Set CIBPE 3366' - 2 sax on top w/ boiler. Water from 3366' to 1365'. 30 sax from 1365' to 1245' water to 885' - 30 sax from 885' to 765'. Water to 390'. Cement to surface from 390'.  
Used 175 sax 60/40 poz mix + 3% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address Attica, KS 67009

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AGVC - John Eck

STATE OF Kansas COUNTY OF Sumner, ss.

Carl W. Durr (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carl W. Durr

(Address) RR#1 Box 16A-3 Milton, KS

SUBSCRIBED AND SWORN TO before me this 12<sup>th</sup> day of November, 19 91

WENDY S. RORABAUGH  
State of Kansas  
My Appt. Exp. Apr. 19, 1992

My Commission Expires: 4-19-92

Notary Public