

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-077020,796 077-20796-0000

LEASE NAME Ethel N. Doll

WELL NUMBER 1

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 24 TWP. 32SRGE. 9 (E) or (W)

COUNTY Harper

Date Well Completed _____

Plugging Commenced 1/17/95

Plugging Completed 1/19/95

#2
TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Attica Gas Ventures

ADDRESS 123 Main, Attica, KS 67009

PHONE# (316) 254-7222 OPERATORS LICENSE NO. 5039

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/17/95 (date)

by Dave Werth (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? yes

Producing Formation Douglas Depth to Top 3482 Bottom 3490 T.D. 3600

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	305	None
				4 1/2	3737	2950

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Sand bottom to 3300, dump 4sx cement with dump bailer, cut and pull casing to 1350, spot 35sx plug, pull casing to 850, 35sx plug, pull casing to 360, circulate cement to surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Attica Gas Ventures

STATE OF Kansas COUNTY OF Barber, ss.

Alan Vratil (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 20 day of January

Glenda Morrison
Notary Public

My Commission Expires: 10/14/98

RECEIVED 1995
STATE CORPORATION COMMISSION
JAN 23 1995
1-23-95
WICHITA, KANSAS
Revised 05