

15-077 - 00097-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Harper County, Sec. 22 Twp 32S Rge. (E) 9 (W)

Location as "NE/CNW/SW" or footage from lines SE SW SE

Lease Owner Beardmore Drilling Company

Lease Name Ellen Well No. 1

Office Address 603 Petroleum Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed December 13 19 53

Application for plugging filed December 13 19 53

Application for plugging approved December 13 19 53

Plugging commenced December 13 19 53

Plugging completed Dec ember 13 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 5034 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red Rock - Shale		0	183	8-3/8	183	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

Heavy Mud from 180' to 5034'

Wood Plug @ 180'

15 Sacks Cement 130' to 180'

Heavy Mud from 35' to 130'

Wood Plug @ 35'

5 Sacks Cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Company  
Address 603 Petroleum Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
I, HEBER BEARDMORE, (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore

603 Petroleum Building, Wichita 2, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of December, 19 53

Leonard P. Tolle

Notary Public.

My commission expires January 28, 1956

24-7368-S 3-53-20M

PLUGGING  
FILE SEC 22 T 32 R 99  
BOOK PAGE 149 LINE 12

DEPT. 2  
12-31-53  
CONSERVATION DIVISION  
Wichita, Kansas

ELLEN NO. 1

SE SW SE  
Section 22-32S-9W  
Harper County, Kansas

Drilled For: Beardmore Drilling Company  
Drilled by: Beardmore Drilling Company

Casing Record:

183' 8-5/8" w/110 Sacks

Drilling Commenced: November 25, 1953  
Drilling Completed: December 13, 1953

Elevation: DF 1468

<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5
Sand	20
Red Rock - Shale	183
Red Bed - Shale	700
Shale - Shells	1100
Shale - Lime	1520
Lime Broken	1680
Lime - Shale	1870
Lime Broken	2000
Lime - Shale	2240
Shale - Lime	2815
Lime - Shale	2940
Shale - Lime	3290
Lime - Shale	3415
Shale - Lime	3566
Shale - Sand	3650
Shale	3745
Shale - Lime	3990
Lime	4060
Lime - Shale	4095
Lime	4210
Lime - Shale	4440
Lime	4580
Lime - Shale	4750
Lime	4838
Cored	4848
Sand	4850
Sand - Shale	4880
Lime - Shale	4915
Shale	4955
Lime - Shale	4990
Lime	5034 T.D.

D & A

TOPS:

Heebner	3417
Douglas	3489
Lime	3968
Marmaton	4242
Mississippi	4430
Kinderhook	4630
Chattanooga	4725
Misner	4760
Viola	4766
Simpson	4832
Arbuckle	4987

RECEIVED  
DEC 31 1958  
12-31-58

- DST #1 - 3516-3566 - Open 45 Min. Shut in 15 Min. 150' Salt Water. BHP 1290#.
- DST #2 - 3808-3840 - Open 1 hr. Shut in 15. Min. Recoveredd 1770' salt water.  
Good Blow. IF 150# FF 920# BHP 1480#.
- DST #3 - 4433-4445 - Open 1 Hr. Weak Blow, shut in 20 min. Recovered 30' Mud  
with few oil specks. IF 12# FF20# BHP50#
- Cored - 4838-4848 - Recovered sand, shaley sand with porosity and no show.

STATE OF KANSAS ss  
COUNTY OF SEDGWICK

**PLUGGING**  
FILE SEC 22 T 32 R 9W  
149 12

I, the undersigned, being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the location above-described, to the best of my knowledge and belief.

Subscribed and sworn to before me this 28th day of December, 1953.

My Commission Expires: January 28, 1956

*Leonard P. Tolle*  
Notary Public