

15-077-20917-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Harper SEC. 21 TWP. 32 RGE. 9W E/W (W)
Location as in quarters or footage from lines:
C SW SW SE 1/4

		X	

Locate Well
correctly on above
Section Platt.

Lease Owner Attica Gas Venture Corp Inc
Lease Name Roderick Well No. 1
Office Address 123 North Main Attica, Kansas 67009
Character of Well (Completed as Oil, Gas or Dry Hole): dry
Date Well Completed 7-8-83
Application for plugging filed _____
Plugging commenced 7-8-83
Plugging completed 7:15 PM 7-8-83
Reason for abandonment of well or producing formation _____
Non productive

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation none Depth to top _____ bottom _____ T.D. 4450

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug set 1350' 35 sacks common 2% Gel 3% C.C.
2nd Plug set 300' 35 Sacks common
3rd Plug set 60' 25 sacks common
10 sacks common in rat hole

RECEIVED
STATE CORPORATION COMMISSION
8-12-83
AUG 12 1983

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sun Oil Well Cementing

STATE OF Kansas COUNTY OF Harper, ss.
P. John Eck (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
123 North Main, Attica, Ks. 67009
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 1983

My Commission expires:

MARILYN DOWNING
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 10-4-85

[Signature] Notary Public.

-DRILLERS WELL LOG-

RODERICK #1
SW SW 3E Sec. 21-32S-9W
Harper County, Kansas

COMMENCED: 7-1-83
COMPLETED: 7-8-83

OPERATOR: Attica Gas Ventures Corp. Inc.

Depth		Formation	Remarks
From	To		
0	262	Redbed	
262	900	Shells-Shale-Redbed	Ran 6 jts of 24# 8 5/8" csg. set @ 258' cemented w/ 200 sks.
900	1360	Shale-Shells	Common 2% Gel-3% CC
1360	1510	Shale	PD @ 7:00 am 7-1-83
1510	2093	Shale-Lime	
2093	4395	Lime-Shale	
4395	4450	Lime	

4450 TD

STATE OF KANSAS)
)
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton, II
James S. Sutton, II-President

Subscribed & Sworn to before me
this fourteenth day of July, 1983

Lola Lenore Costa
Lola Lenore Costa-Notary Public

My Commision expires November 21, 1984

