

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED OCT 27 2003 KCC WICHITA

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: American Warrior, Inc. Address: P.O. Box 399 Phone: (620) 275-2963 Operator License #: 4058 Type of Well: Oil Docket #: The plugging proposal was approved on: 10-22-03 by: Richard Lacy (KCC District Agent's Name) Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No Producing Formation(s): Cherokee Depth to Top: 4170' Bottom: 4271' T.D. 4300'

API Number: 15-135-30260001 (drilled 1966) Lease Name: Mellick Well Number: A-1 OWWO Spot Location (QQQQ): 150 - W - SW - NW 1980 Feet from [X] North / [] South Section Line 510 Feet from [] East / [X] West Section Line Sec. 35 Twp. 18 S. R. 21 [] East [X] West County: Ness Date Well Completed: 3-9-78 Plugging Commenced: 10-22-03 Plugging Completed: 10-22-03

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Cherokee, oil/water, 4181', 4186', 8 5/8, 246', None. Row 2: (blank), (blank), (blank), (blank), 4 1/2, 4295', None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Mixed & pumped 20 sacks cement with 200# of hulls down casing and displaced to perfs (4181-86'), shut in with 700 psi, perforate @ 650', mix & pump 120 sacks cement with 100# of hulls and shut in with 400 psi, pump 40 sacks down 8 5/8 braden head and pressure up to 400 psi, well plugged.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382 Address: Ness City, KS 67560 Name of Party Responsible for Plugging Fees: American Warrior, Inc. State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God. (Signature) [Signature] (Address) 210 Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 23rd day of October, 20 03. Bernice Moore Notary Public My Commission Expires: 2/7/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

