

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,329-0000

LEASE NAME Harley Price

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

660 Ft. from S Section Line

3300 Ft. from E Section Line

LEASE OPERATOR John J. Darrah, Jr.

SEC. ___ TWP. ___ RGE. ___ (E) or (W)

ADDRESS 412 E. Douglas, Suite One, Wichita, Ks. 67202 COUNTY Ness

PHONE# (310-685-4467) OPERATORS LICENSE NO. 5088

Date Well Completed ___

Character of Well oil

Plugging Commenced 5-19-87

(Oil, Gas, D&A, SWD, input, Water Supply Well)

Plugging Completed 7-21-87

Did you notify the KCC District Office prior to plugging this well? ___

Which KCC Office did you notify? One

Is ACO-1 filed? ___ If not, is well log attached? ___

Producing Formation ___ Depth to Top ___ Bottom ___ T.D. 4231'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	416'	None
				5-1/2"	4217'	2,356.78'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4,085' and 5 sacks cement. Shot casing at 2300'. Pulled 61 joints of 5-1/2" casing. Squeezed well with 400# hulls, 25 sacks gel, and 200 sacks 60/40 pozmix cement., with 6% gel. Maximum pressure was 1000 psi and shutin 400 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
(Address) James W. Rockhold
Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 22nd day of July, 1987

My Commission Expires: ___

STATE NOTARY PUBLIC
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. Jul 26 1987

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
JUL 23 1987
7-23-87 Form CP-4
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

15 135-22329-0000

COMPANY: JOHN JAY DARRAH, JR.
CONTRACTOR: MALLARD DRILLING CO., INC.
405 Century Plaza
Wichita, Kansas 67202

WELL NAME: #1 (Harley) Price
DESCRIPTION:
C SE SW
35-18S-21W

RIG NO.: 1

COUNTY: Ness

TOTAL DEPTH: 4218'

ELEVATION: 2160 KB

COMMENCED: January 15, 1983

COMPLETED: January 21, 1983


CASING RECORD:

10 jts. 8 5/8" 23#
113 jts. 5 1/2" 10#


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, shale and lime	0	784	Ran 407' new 23# 8 5/8" surface casing; set and cemented at 416' with 250 sacks 60/40 pozmic, 2% gel, 3% CaCl. Cement circulated. Plug down at 7:30 p.m. January 15, 1983.
Sand	784	1005	
Shale and lime	1005	1362	
Anhydrite	1362	1395	
Shale w/lime streaks	1395	3640	
Lime	3640	4218	
			Ran 113 jts. new 5 1/2" 10# casing; set with 100 sacks 60/40 pozmix with 8 bbl. salt flush. Job completed at 1:45 a.m., January 21, 1983. Casing set at 4217.

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify that this is a true and correct copy of the log of the #1 Harley Price well, to the best of my knowledge.


John Jay Darrah, Jr., President

SUBSCRIBED AND SWORN to before me this 28th day of January, 1983.


Dianne R. Fowler, Notary Public

My Commission Expires:
August 25, 1984

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1987
5-13-87
CONSERVATION DIVISION
Wichita, Kansas