

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 1 1963  
 5-1-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. T. L. Dix of Skelly Oil Co. has this

date requested permission to plug the following described well:

Mr. Dix guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Co.

Complete Address: 1020 North Main, Hutchinson, Kansas

Lease Name: Lonker Well No. # 5

Location: C N/2 N/2 NW Sec. 1 Twp. 33 Rge. 13 (E) (W) W

County Barber Total Depth 4585 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Dix was instructed to plug the well as follows:

475' of 8 5/8" surface pipe, cement circulated with 275  
sacks. Fill hole with mud to 240', 1st cementing plug,  
1/4 sack hulls, cement with 20 sacks. Fill hole with mud  
to 40', 2nd cementing plug, 1/2 sack hulls, cement with 10  
to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent