

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-01035-00-01  
Spot: SENWNWNE Sec/Twnshp/Rge: 2-22S-19E  
4660 feet from S Section Line, 2270 feet from E Section Line  
Lease Name: UNIT 3 Well #: P 22  
County: ANDERSON Total Vertical Depth: 864 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	816		0 SX
SURF	7	20		0 SX

Well Type: EOR UIC Docket No: E05363.39 Date/Time to Plug: 02/13/2013 12:00 AM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: STERLING BARKER Company: Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string out and top off well with cement. Tie onto tubing and squeeze cement until desired amount of pressure is achieved. Cut well off 3' below surface.

Plugging Proposal Received By: FORREST SUTHERLAND WitnessType: NONE  
Date/Time Plugging Completed: 07/22/2013 12:00 AM KCC Agent: FORREST SUTHERLAND

Actual Plugging Report:

2-13-13-- TIED ONTO WELL AND SQUEEZED CEMENT UNTIL PRESSURE STARTED TO CLIMB. INSERTED CEMENT PLUG IN TUBING AND PUMPED IT DOWN TO 650'. MIDWEST SURVEYS BLEW TUBING OFF AT 640'- PULLED IT OUT. 7-22-13-- RAN WORKSTRING TO 625' INSIDE 4" AND PUMPED CEMENT TO SURFACE. RAN WORKSTRING ON BACKSIDE OF 4" AND PUMPED CEMENT TO SURFACE. 200 SACKS USED TO PLUG WELL.

Perfs:

Top	Bot	Thru	Comments
840	860		
RECEIVED SEP 16 2013 KCC Chanute Dist. #3 FS			

Remarks:

Plugged through: TBG

KCC WICHITA

SEP 20 2013

RECEIVED

District: 03

Signed

*[Signature]*  
10/15/13 (TECHNICIAN)  
cc to WMC 9/24/13