

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20767-00-02
Spot: NWSWSWSE Sec/Twnshp/Rge: 24-11S-26W
344 feet from S Section Line, 2415 feet from E Section Line
Lease Name: WOLF T Well #: 2
County: GOVE Total Vertical Depth: 4700 feet

Operator License No.: 34515
Op Name: 6G TWISTER, INC.
Address: PO BOX 1565
GILLETTE, WY 82717

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2002		
CIBP		3725		
PKR	2.375	1741		
PROD	4.5	4190		100 SX
SURF	8.625	345		175 SX
T1	2.375	1741		

Well Type: SWD UIC Docket No: D28032.0 Date/Time to Plug: 08/19/2013 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: LEE GREENE Company: 6G TWISTER Phone: (307) 682-7380

Proposed 08-19-2013: Ordered 150 sx 60/40 pozmix 4% gel cement.
Plugging 10-02-2013: Ordered 50 sx 60/40 pozmix 4% gel cement.
Method: 8 5/8" surface casing set at 345' w/175 sx cement. 4 1/2" production casing set at 4190' w/100 sx cement.
TD 4700'. DV tool at 1150' w/225 sx cement. Casing squeezed at 2000' and 1720' - 1750' w/375 sx cement. Squeezed at 1150' w/75 sx cement. CIBP at 3725' and 2002' w/1 sx cement on top. Cedar Hills perforations at 1800' - 1900'. 2" J-55 unlined tubing cemented in 4 1/2" casing on 09-11-2002 and set to 1741'. Cement circulated to surface

Plugging Proposal Received By: CASE MORRIS WitnessType: PARTIAL
Date/Time Plugging Completed: 10/02/2013 1:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

08-19-2013: Ordered 150 sx 60/40 pozmix 4% gel cement. Ran 1" tubing to 1800'. Could not pump into. Pulled 1" tubing to 600' and pumped 30 sx cement. Cement to surface. Connected to 8 5/8" surface casing and pumped 20 sx cement. Maximum pressure 200 psi. Connected to 2 3/8" tubing and pumped 15 sx cement. Allied Cement ticket # 138128. The procedure was not witnessed by KCC staff.
09-09-2013: KCC staff checked cement level in 2 3/8" tubing/casing at 400' from surface.
10-02-2013: Ordered 50 sx 60/40 pozmix 4% gel cement. Ran 1" poly-pipe to 380' and pumped 25 sx cement. Cement to surface. Pumped 25 sx cement into cellar. SOS Cement ticket # 1117
GPS: 39.07538N -100.15663W

Perfs:

Top	Bot	Thru	Comments
1800	1900		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: ALLIED CEMENT TICKET # 138128 AND SOS CEMENT TICKET # 1117

Plugged through: TBG

OCT 09 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

OCT 04 2013

Form CP-2/3