

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20830-00-00  
Spot: SENWNENE Sec/Twnshp/Rge: 28-25S-40W  
4642 feet from S Section Line, 677 feet from E Section Line  
Lease Name: BLACKWELL Well #: 1-28  
County: HAMILTON Total Vertical Depth: 5600 feet

Operator License No.: 34289  
Op Name: ADAMS AFFILIATES, INC.  
Address: 1437 S. BOULDER, STE 930  
TULSA, OK 74119

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2300		WITH 2 SX CMT
CIBP		3908		
CIBP		4500		
CIBP		4606		
CIBP		5030		
CIBP		5500		
PROD	5.5	5599	0	WITH 235 SX CMT
SURF	8.625	856		WITH 425 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/29/2013 1:30 PM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: CHARLES CRAWFORD Company: ADAMS AFFILIATES Phone: (918) 691-4905

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/29/2013 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2300' WITH 2 SX CMT. RUN CBL. NO CMT ABOVE 2300'. PERFORATE AT 2000'. INJECTION RATE 2 BPM @ 100#. PUMP 50 SX CMT WITH 20 BALL SEALERS & 125# HULLS IN THE LAST 25 SX CMT. WITH BALLS & HULLS ON PERFS, PRESSURE INCREASED FROM 100# TO 400# LEAVING 25 SX CMT OUTSIDE THE 5 1/2" CASING & 25 SX CMT INSIDE WITH 5 1/2" CASING. FULL CIRCULATION OUT ANNULUS. PERFORATE AT 900'. CIRCULATE CMT TO SURFACE WITH 215 SX CMT LEAVING 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
5534	5546		
5310	5356		
4618	4626		
4564	4574		
3922	4040		
2515	2570		

KCC WICHITA  
SEP 12 2013

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

RECEIVED

Plugged through: CSG

RECEIVED

District: 01

SEP - 4 2013

Signed

*Ken Jehlik*  
10/8/13

(TECHNICIAN)

KCC DODGE CITY

AM