

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20330-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 27-30S-41W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: WILLIAMS Well #: 1
County: STANTON Total Vertical Depth: 5455 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5000		WITH 2 SX CMT
CIBP		5300		WITH 2 SX CMT
PROD	5.5	5454	2200	WITH 250 SX CMT
SURF	8.625	1559		WITH 650 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/11/2013 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 5300' CIBP @ 5000'. PLUG AT 1570' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 09/11/2013 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 5300' WITH 2 SX CMT. CIBP @ 5000' WITH 2 SX CMT. 1ST PLUG AT 1570' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5374	5386		
5074	5284		

KCC WICHITA
SEP 25 2013
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED
SEP 18 2013

Signed Michael Maier
10/18/13 (TECHNICIAN)

KCC DODGE CITY