

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-193-20162-00-01  
Spot: SES Sec/Twnshp/Rge: 34-9S-33W  
660 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: WIENS Well #: 2  
County: THOMAS Total Vertical Depth: 4730 feet

Operator License No.: 4967  
Op Name: BERENERGY CORPORATION  
Address: PO BOX 5850  
DENVER, CO 80217

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	367		280 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/02/2013 2:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DALE MUTTLBAUER Company: ALLIED CEMENT COMPANY Phone: (307) 689-9032

Proposed Plugging Method: Ordered 370 sx 60/40 pozmix 4% gel cement, 9 sx gel and 600 # hulls.  
Perforations: 4172' - 4178', 4164' - 4169', 4128' - 4134', 4060' - 4068'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/02/2013 12:00 AM KCC Agent: TOM CULLEY

Actual Plugging Report:

Perforated at 2700', 1670' and 300'.  
Ran tubing to 3980' and pumped 9 sx gel followed by 50 sx cement w/500 # hulls.  
Pulled tubing to 2700' and pumped 125 sx cement w/100 # hulls.  
Pulled tubing to 1668' and pumped 125 sx cement . Circulated cement to surface.  
Pulled tubing to 340' and pumped 60 sx cement . Filled 8 5/8" x 4 1/2" casing.  
Topped off 4 1/2" casing with 10 sx cement.  
  
GPS: 39.22158 -100.99313

Perfs:

Top	Bot	Thru	Comments
4620	4622		
4304	4307		
4258	4260		
4172	4178		
4164	4169		
4128	4134		
4060	4068		

KCC WICHITA

Remarks: ALLIED TICKET # 60338


SEP 17 2013

Plugged through: TBG

RECEIVED

District: 04

Signed

  
10/18/13 (TECHNICIAN)

CM

SEP 12 2013