

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02993-00-02
Spot: SWSNWSW Sec/Twnshp/Rge: 10-14S-17W
1352 feet from S Section Line, 4388 feet from E Section Line
Lease Name: CHRISTINA A Well #: 2
County: ELLIS Total Vertical Depth: 3590 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	2.875	3441		200 sx
PROD	4.5	3590		100 SX
SURF	8.625	172		145 SX

Well Type: SWD UIC Docket No: E27411.1 Date/Time to Plug: 08/22/2013 9:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Revd. from: CURTIS GABEL Company: BEREXCO LLC Phone: (785) 623-0546

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement; 400 # hulls.
Casing leaks- 600' - 2990'.
PBTD- 3561'
Perforations- 3458' - 3461'
GPS: 38.84597 -099.20353
1385' FSL 4299' FEL SW SE NW SW

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/22/2013 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Berexco ran in hole with 1" tubing to 3300'. Rigged to tubing and mixed and pumped 45 sx cement.
Pulled tubing to 1650'. Allied rigged to tubing and mixed and pumped 120 sx cement.
Pulled tubing. Rigged to 2 7/8" tubing with a swedge and valve and pumped 30 sx cement w/100 # hulls mixed in to pressure with 400 psi. 400 psi shut in pressure.
Rigged to 4 1/2" casing between 2 7/8" casing. Instant pressure of 200 psi. 200 psi shut in pressure.
8 5/8" casing full of cement.

Perfs:

Top	Bot	Thru	Comments
3458	3461		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: ALLIED CEMENTING TICKET # 56995

SEP 09 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed [Signature]
10/18/13 (TECHNICIAN)

cc to UIC 9/10/13

CM