

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21412-00-00
Spot: NE Sec/Twnshp/Rge: 30-24S-22W
725 feet from N Section Line, 2295 feet from E Section Line
Lease Name: ZUEGE-NIETLING Well #: 1
County: HODGEMAN Total Vertical Depth: 5000 feet

Operator License No.: 7567
Op Name: BOWLES, JACK
Address: PO BOX 3285
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1635		WITH 400 SX CMT
PROD	5.5	4996	0	WITH 750 SX CMT
SURF	8.625	380		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2013 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: TIM GILLOGLY Company: JACK BOWLES Phone: (785) 639-5159

Proposed Plugging Method: RUN TBG TO 4710' & PUMP 14 SX GEL THEN 35 SX CMT WITH 150# HULLS. PULL TBG TO 1640' & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/20/2013 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4705' & PUMP 14 SX GEL THEN 50 SX CMT WITH 150# HULLS. PULL TBG TO 1625' & PUMPED 190 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 17 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4718	4732		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

SEP 10 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Michael Maier
10/18/13

(TECHNICIAN)

RECEIVED

SEP - 6 2013

KCC DODGE CITY

Form CP-2/3

BMH