

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-077-00093-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1966
3-28-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Curley Brau of E. K. Edmiston Drilling has this
date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 501 First National Bank Bldg., Wichita, Ks.

Lease Name: Fetrow "B" Well No. # 1

Location: C SE SW Sec. 6 Twp. 32 Rge. 9 (E) (W) W

County Harper Total Depth 4453' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brau was instructed to plug the well as follows:

700' of 10 3/4" surface pipe, cement circulated. Fill hole
with drilling mud to 300', 1st cementing plug, bridge with hulls
and cement with 30 sacks. Fill hole with drilling mud to 40', 2nd
cementing plug, bridge with hulls, and cement with 15 sacks to
base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving