

OB
R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 81-45

LOCATION CE/R - NE-SE

SEC. 22 TWP. 32 RGE. 13-W

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 2 Lease Hildebrand

Operator Champion Refining Co Address Box #167 - Ellinwood - Kansas

Field _____ County Baebey

Total Depth 5120 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 393 ft. Circulated with cement.
5 1/2" casing set at 5110 ft. Plugged back from bottom
to 4960 ft with cement - Mixed 5 sacks of cement
at 4960 ft - Shot of x Pulled 900 ft of 5 1/2" casing - Filled
with mud to 2600 ft - Set Rock Bridger & 20 sacks cement
at 2500 - Mud to 2075 - Plug x 10 sacks of cement at
the surface - Hoggatt & Lynch - Plugging Contractors

C. D. Storch -
District Conservation Agent

Date 2 - 19 - 49

RECEIVED

Conservation Div.

FEB 23 1949

STATE CORPORATION
COMMISSION
KANSAS

PLUGGING
FILE SEC 22 TWP 32 R 15W
BOOK PAGE 81 LINE 45