

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

AUG 29 1975
8-29-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Atlantic Richfield Co

Complete Address 1112 11th St Woodward, OK

Lease Name T.L. Welsh D Well No. 2-SWD

Location SW/SW/NE Sec. 18 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 4840

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Lillard Casing Pulling Co

Address Box 926 Woodward, OK License No. 618

Operation Completed: Hour 3:00 PM Day 23 Month 8 Year 1975

The above well was plugged as follows:

320 ft 10 3/4 surface cement circulated. 4839 ft 5 1/2 long string
cemented with 200 sacks. Top perf. 4760 ft. Pump 35 sacks cement to
4385 ft. Pulled 3919 ft 5 1/2. Pump 2 sacks hulls, 15 sacks gel,
50 sacks cement from 370 ft, to 270 ft. Mud to 40 ft, plug, 15 sacks
cement to surface. Welded plate on S.P.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 9/3/75
INV. NO. 1855-62