

15-007-30375-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1965
10-14-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sunray DX Oil Company

Complete Address: 300 Union National Bldg., Wichita, Kansas

Lease Name Vaughn DeGeer "A" Well No. # 1

Location C SE NE Sec. 33 Twp. 32 Rge. 15 (E) (W)

County Barber Total Depth 5266'
5270'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drilling Company

Address: Route 2, Great Bend, Kansas License No. _____

Operation Completed: Hour 7:30 PM Day 12th Month Oct. Year 1965

The Above well was plugged as follows:

227' of 13 3/8" surface pipe, cement circulated. Hole was filled with
drilling mud to 200', 1st cementing plug, bridged solid with drv cement
and hulls on fluid at 200', and cemented with 50 sacks. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged solid with drv
cement and hulls on fluid at 40', and cemented with 30 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 10/14/65

INV. NO. 1974-u