

*R* *CP3*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 82-22

LOCATION 7W/4

SEC. 16 TWP. 32 RGE. N:W

Dry Hole \_\_\_\_\_ Abandoned Oil Well <sup>x 920</sup> X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 12 Lease Hildebrand

Operator Franklin Refining Co Address Box #552 - Enid - Oklahoma

Field \_\_\_\_\_ County Barber

Total Depth 5002 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 465 ft - Circulated with cement.  
8 1/2" 800 ft - Circulated with cement - 5 1/2 casing  
set at 5002 ft. Plugged back lower bottom to 4955 ft  
with loose wellbore pipe & chat - Dumped 4 sacks cement at 4955 ft  
Shot off & Pulled the 7" casing - Filled with mud to 250 ft.  
Arch bridge & 20 sacks of cement at 250 ft - Mud to 25 ft.  
Plug & 10 sacks of cement at the surface

*C. M. [Signature]*  
District Conservation Agent  
Conservation Div.

Date 3-3-1928

STATE CORPORATION  
COMMISSION  
KANSAS

**PLUGGING**  
FILE SEC 216 T 32 R 152  
BOOK PAGE 82 LINE 22