

DISTRICT CONSERVATION AGENT'S REPORT

Handwritten initials and a large stylized 'R' with a checkmark.

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 52-15

LOCATION C.S. 1/4 - NW - SW

SEC. 16 TWP. 32 RGE. 15-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Baird

Operator Chauplin Refining Co. Address Box #552 - Enid - Okla.

Field _____ County Barber

Total Depth 5011 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 10 3/4 - 4920 ft. Circulated with cement -
5th casing at 5011 ft. - Cemented with 385 sacks cement.
Plugged back to 4975 ft with chat - then mixed
5 sacks of cement at 4975 ft - Shot off & pulled the
5th casing - Mixed to 300 ft - Set Rock Bridge &
20 sacks of cement at 300 ft. Mixed to 36 ft -
Plug 10 sacks cement at the surface -
P. Pulling, Inc. - Plugging Contractor*

PLUGGING
FILE SEC. 26 T 32 R 15 W
BOOK PAGE 52 LINE 15

RECEIVED
STATE CORPORATION COMMISSION
JAN 23 1951
CONSERVATION DIVISION
Wichita, Kansas

C. M. Stough
District Conservation Agent

Date 1-18-51