

*14*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Time Petroleum Co.  
Complete Address: 815 Union National Wichita, Kansas.  
Lease Name Woods Well No. 1  
Location SW SW NE Sec. 16 Twp. 32S Rge. (E) (W) 15  
County Barber Total Depth 4862  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated: \_\_\_\_\_  
Plugging Contractor: Smith & Smith.  
Address: Box 8, Cushing, Oklahoma. License No. 205  
Operation Completed: Hour 5:10PM Day 7 Month July Year 1962

The Above well was plugged as follows:

Description of hole: 5 1/2" pipe set on bottom 4242" perforation between 4722" and 4727". 270' 8 5/8" surface pipe. Plugged as follows: Sanded to 4242, 10 sacks of cement, heavy drilling mud to 295', 10' rock bridge set and 20 sacks cement, filled with heavy drilling mud to 40'. Rock bridge and 10 sacks cement to bottom of cellar.

JUL 16 1962  
7-16-62  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 7/10/62  
INV. NO. 5349-W

Signed: Herman Justus  
Well Plugging Supervisor